
	ICAR- Central Potato Research Station Kufri (Shimla Hills) – 171012 HP.	
---	--	---

QUOTATION

Sealed quotations from registered contractors for executing the above job/work of “Repair of boundary wall at CPRS, Kufri” (as per details attached) are hereby invited on the following terms & conditions:

1. The quotation must be sent strictly as per instructions contained in this letter duly signed & stamped in Annexure-I failing which no cognizance for incomplete quotation will be given.
2. The quotation should be in a sealed cover superscribed with “Repair of boundary wall at CPRS, Kufri” addressed to **“Head, Central Potato Research Station, Kufri, Shimla-171012.”**
3. The quotation should reach in this office up to **3.00 PM on 07.11.2016** which will be opened on the same day at 3.30 PM in the presence of the contractors or their representatives.
4. In case of any cutting/correction & over writings, the same may be initialed.
5. Contractor is allowed to visit the site at his own expenses before sending the quotation, if so, desired by him.
6. The rates must be quoted item-wise/per unit **with a grand total at the end of work detail**. The sale tax/service tax & other charges, if any, may either be shown separately or be included in the rates quoted.
7. 10% security of the total contract price quoted will have to be deposited at this Institute before starting the work which will be released only after six months from the date of completion of work.
8. The work is required to be completed in all respect within 120 days from the date of work award.
9. If the contractor, the people at work shall break, deface injure or destroy building, enclosure water pipes, cable grounds contiguous to the place where the work is being executed/carried out, the Contractor would require to make it good/re-construct the same at his own expense failing to do so, the damages shall be repaired by the Institute and the expenses will be deducted from any sums due or which may become due to the Contractor.
10. Final payment will be made only after completion of work to the satisfaction of the OIC (Estate) or a committee constituted for the purpose.
11. No material will be issued from this Institute for this work.
12. If the contractor, use Institute water for this work(s), 1% water charges will be deducted from the total bill of the contractor of this work(s).

13. The quotation should accompany with an earnest money of Rs. 10, 000/- in the shape of **banker Cheque/bank draft drawn in favour of ICAR-Unit-CPRI, Shimla. Quotations without EMD will not be entertained at any cost.**
14. In the event of failure/refusal of the contractor to execute the awarded work, the earnest money deposit will stand forfeited and the contractor can be debarred for any work in CPRI.
15. The work shall be executed strictly as per specification/drawing given in the details of work and on the instructions of the OIC (Estate), CPRI, Shimla.
16. Authority reserves the right to accept or reject any or all quotations without assigning any reason.
17. Quoted rates should be valid up to 06 months or 31st March, 2016 whichever is later.



(Vinod Kumar)
Head

Encl. As above

ESTIMATE

Name of work:- Repair of boundary wall at CPRS Kufri, Shimla .

SN	Item of work	Qty	Rate	Unit	Amount (Rs)
1	Demolishing brick work manually/by mechanical mean including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer- in-charge (A) In cement mortar	2.50 m3		cum	
2	Dimantling steel work manually/ by mechanical means in built up sections without dismembering and stacking within 50 metres lead as per direction of Engineer in charge	75.0 Kg		kg	
3	Earth work in excavation by mechanical means(Hydraulic excavator) / manual means in foundation trenches or drain (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms , lift up to 1.5 m , including getting out the excavated soil as directed , with in a lead of 50 m (A) All kinds of soil	40.00 m3		cum	
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering ad shuttering -All work up to plinth level				
4A	1:5:10 (1 cement : 5 coarse sand :10 graded stone aggregate 40 mm nominal size)	7.00 m3		cum	
4B	1:2:4 (1 cement : 2 coarse sand :4 graded stone aggregate 20 mm nominal size)	2.50m3		cum	
5	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in cement mortar 1:6 (1 cement :6 coarse sand)	17.50m3		cum	
6	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth plinth levl upto floor V level in all shapes and sizes in cement mortar 1:6 (1 cement :6 coarse sand)	25.00m3		cum	
7	12 mm thick cement plaster of mix 1:6 (1 cement : 6 fine sand)	140.00m2		sqm	
8	15 mm cement plaster on the rough sides of single or half brick wall of mix 1:6 (1 cement : 6 fine sand)	140.00m2		sqm	
9	Structural steel work riveted , bolted or welded in built up section ,trusses and framed work ,including cutting	450 Kg		Kg	

	, hoisting , fixing in position and applying a priming coat of approved steel primer all complete .				
10	P/F G.I. barbed wire of approved brand (minimum weight not less than 9.38 kg per 100 meter) with G.I. staples etc. complete .	800.00 m		mtr	
11	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @3.84 kg/10 sqm)	280.00 m2		sqm	
12	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade (a) Two or more coat on new work	20.0 m2		sqm	
			Total	Rs	
	Add 33 % cost index on rates of D.S.R. 2014		(+)	Rs	
		Grand	Total	Rs	

Rupees

Term and condition-:

1-No electricity will be provided by the Institute.

2-All dismantled material should be disposed at the dumping site of Municipal Corporation out of the CPRS campus.

No extra payment will be made for the disposing the above material.

Annexure-I

To

The Head,
Central Potato Research Station,
Kufri, Shimla-171012 (HP).

Ref: Your quotation No.F.5 (3)/KS/2016-17/_____ dated _____ for “Repair of boundary wall at CPRS, Kufri”

Sir,

Having examined your above mentioned quotation letter including details of work to be executed (DNIT), the receipt of which is hereby duly acknowledged, I, the undersigned offer to execute the above work in conformity with the said quotation document for the sum as shown against each item of work and at a total of Rs. _____.

I, hereby undertake if my quotation is accepted, to execute the work in accordance with the details of work, as specified in the details of work after fulfilling all the applicable requirements incorporated in the above referred quotations.

If the bid/quotation is accepted I will provide you security deposit as per clause No.7 inserted in quotation letter for a sum equivalent to 10% of the contract price.

I agreed to abide by this quotation for the validity period specified or for the subsequently period, if any agreed to by me and it shall remain binding upon me and may be accepted at any time before the expiration of the period.

Until a formal contract work order is prepared and executed, this offer together with your written acceptance thereof and your notification of work award, shall constitute a binding contract between us.

I understand that you are not bound to accept the lowest or any bid you may receive.

Date: _____

Place: _____

(Signature of the contractor)
With name, address, seal
and registration No._____

**Note: Please enclose the photocopy of registration, PAN Card
Otherwise quotation will be rejected.**